Abstract Notification dated 27th November 1939.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for constructing Kannada Primary School Building at Magadi, published in pages 2400-2402 of Part VI of the *Mysore Gazette*, dated 30th November 1939.

The last date for the receipt of the tender is 2 P.M. on 11th December 1939. Duplicate challan for having credited the deposit amount of Rs. 280 into the Treasury under 17 (*a*) P.W. Deposits should accompany each tender.

Abstract Notification dated 27th November 1939.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for constructing a building for the Kannada Primary School at Hadripura, Dodballapur Taluk, published in pages 2403-2405 of Part VI of the *Mysore Gazette*, dated 30th November 1939.

The last date for the receipt of the tender is 2 P.M. on 11th December 1939. Duplicate challan for having credited the deposit amount of Rs. 150 into the Treasury under 17 (*a*) P.W. Deposits should accompany each tender.

Abstract Notification dated 27th November 1939.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for constructing the Kannada Primary School Building at Nelamangala, published in pages 2405-2407 of Part VI of the *Mysore Gazette*, dated 30th November 1939.

The last date for the receipt of the tender is 2 P.M. on 11th December 1939. Duplicate challan for having credited the deposit amount of Rs. 280 into the Treasury under 17 (*a*) P.W. Deposits should accompany each tender.

Abstract Notification dated 27th November 1939.

The attention of the public is hereby invited to the detailed notification, inviting sealed tenders for constructing the Kannada Primary School at Hosakote, published in pages 2448-2450 of Part VI of the *Mysore Gazette*, dated 30th November 1939.

The last date for the receipt of the tender is 2 P.M. on 11th December 1939. Duplicate challan for having credited the deposit amount of Rs. 280 into the Treasury under 17 (*a*) P.W. Deposits should accompany each tender.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 30th November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 23rd December 1939 "for the work of providing flushing latrines of 24 seats with underground drainage to the Municipal sewer for the Sub-Jail, Mysore." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 385 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of providing flushing latrines of 24 seats with underground drainage to the Municipal sewer for the Sub-Jail, Mysore," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantity of work for providing Flushing Latrines of 24 seats with Underground Drainage to the Municipal Sewer for the Sub-Jail, Mysore.

No.	Items of work	Unit	Quantity	Rate
	FLUSHING ARRANGEMENTS.			Rs. a. p.
1	Providing, laying and jointing 7″ S.W. channels and pipes with cement concrete bed and sides	R.ft.	104	
2	Constructing cement concrete drain above channel and up to 2′ height, cement plastering and rounding edges.	,,	104	
3	Making cement concrete H.C. Pan with necessary iron rod support, filling cement concrete alround Pan and H.C. Compartment and plastering with cement mortar	Each	24	
4	Providing and fixing 15 gallons automatic flushing tank including grooving in wall and redoing	,,	4	
5	Providing and fixing angle iron brackets for flushing tanks including wall bore and redoing, bed slabs, etc.	,,	4	
6	Providing and fixing $1\frac{1}{2}$″ Galvanized flush pipe with necessary fittings including grooving in wall and redoing	,,	4	
7	Wall bore and redoing	,,	26	
8	Providing and fixing cement foot rests	Pair	24	
9	Providing, laying and jointing $\frac{3}{4}$″ G.I. pipe with fittings including E.W., etc., complete and connection to flushing tanks	R.ft.	160	
10	Providing water connection with $\frac{3}{4}$″ and $\frac{1}{2}$″ Galvanized pipe with fittings, laying and jointing wall and floor grooving and redoing complete	Each	24	
11	Providing and fixing $\frac{3}{4}$″ G.M. gland cocks	,,	8	
12	Do $\frac{1}{2}$″ S.D. bib cocks	,,	24	
13	Constructing gland cock cistern and providing and fixing C.I. road box	,,	2	
14	Removing and relaying water pipe	,,	1	
15	Providing and fixing 9″×6″ S.W.Gully traps with cement concrete bed	,,	2	
16	Constructing Inspection Chamber as per design, complete including providing and fixing 24″×18″ C.I. cover and frame up to 3′ height	,,	2	
	DRAINAGE ARRANGEMENTS.			
1	Providing and laying and jointing 6″ S.W. pipe in cement mortar	R.ft.	1,558	
2	Wall bore and redoing	Each	1	
3	Man-hole bore and redoing and making drains	,,	3	
4	Earthwork excavation in hard and gravelly soil, refilling trench and watering and tamping complete up to 8′ depth	C.yds.	697	
5	Excavating and removing soft rock	,,	100	

No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
6	Constructing man-hole 3′ dia. inside as per design complete including providing and fixing 21″ dia. C.I. man-hole cover and frame up to 3′ height	Each	2	
7	Do 4′ dia. and as above with necessary C.I. steps 3′ to 4′ height	,,	2	
8	Do 4′ to 5′ depth as above	,,	2	
9	Do 5′ to 6′ deep as above	,,	3	
10	Do 7′ to 8′ deep as above	,,	1	
11	Repairing road crossing with fresh jelly consolidating, etc.	R.ft.	18	
12	Encasing 6″ pipe line with cement concrete alround ..	,,	20	
13	Dismantling concrete benches existing man-hole and redoing	Each	1	

K. S. HUTCHA RAO,
Sanitary Engineer.

KOLAR DIVISION.

Notification dated 28th November 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 22nd December 1939, for improving the Feeder Channel to Devar Mallur, Major Tank, Register No. 32, Sidlaghatta Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for Improving the Feeder Channel to Devar Mallur Major Tank." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for earnest money of Rs. 140, paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd December 1939 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.